SHIMOGA DIVISION.

Dated 11th April 1912.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 28th April 1912, for constructing a 3rd class travellers' bungalow at Harige, Sagar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1913.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a 3rd class travellers' bungalow at Harige, Sagar Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract.

Serial No.	*Items of work*	*Per*	*Quantity*
1.	Earthwork excavation and filling basement ...	C. yd.	80
2.	Burnt brick in chunam foundation and basement ...	C. ft.	3,318
3.	Burnt brick in chunam superstructure ...	"	4,568
4.	Burnt stone slabs, dressed and fixed ...	S. ft.	398
5.	Burnt brick in chunam archwork ...	C. ft.	53
6.	Cut stone pillars, complete ...	No.	6
7.	Chunam plastering ...	Sq.	83·68
8.	White and colourwashing ...	"	83·68
9.	Teakwood work wrought and put up with wood oiling ...	C. ft.	241·04
10.	Roofing with 1st class Mangalore tiles, on teak reepers, etc., complete ...	Sq.	33·54
11.	Ceiling with Mangalore pattern play tiles ...	"	8·75
12.	Mangalore ridge tiles set in mortar and cement pointing, complete ...	R. ft.	153
13.	Mangalore ventilating tiles ...	No.	8
14.	Teakwood panelled door including iron clamps, etc., complete ...	S. ft.	155
15.	Teakwood double doors ...	Lump sum	Rs.
16.	Teakwood windows glazed inside and panelled outside ...	S. ft.	54
17.	Teakwood circular ventilators with glazed shutters, etc., complete ...	"	14
18.	Teakwood rectangular ventilators with glazed shutters, etc., complete ...	"	19
19.	Teakwood battened doors with frames, etc., complete ...	"	104
20.	Teakwood battened windows, complete ...	"	14
21.	Teakwood eaveboard, plain ...	R. ft.	169
22.	Flooring with 1st class Mangalore tiles on 3" concrete bed and cement pointing ...	Sq.	7·10
23.	Flooring with Cuddappa slabs on 3" concrete bed and cement, pointing complete...	"	8·59
24.	Flooring with gravel, 6" thick, well watered and rammed	C. yd.	5
25.	Wood oiling ...	Sq.	5·00
26.	Painting (silicate) ...	"	8·00
27.	Providing two cisterns in bath rooms with drain pipes, etc., complete ...	Lump sum	Rs.
28.	Do do pestel and mortar ...	Do	
29.	Constructing fire place ...	Do	
30.	Clearing site and levelling ground ...	Do	

B. GARUDACHARYA, *Executive Engineer.*

2 H